

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

DRM W PUNE acting for and on behalf of The President of India invites E-Tenders against Tender No **DRM-W-PA-E-Tend-2024-S-38** Closing Date/Time 15/04/2025 15:15 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	15/04/2025 15:15	Date Time Of Uploading Tender	21/03/2025 12:29
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	96144750.75	Tendering Section	SR.DEN S
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	630700.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	01/04/2025		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-A -MS Items Provision of Cover Shed for 21 Wagons (315 x 14= 4410 sqm) of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							54701907.13	Above/ Below/Par
1	Please see Item Breakup for details.				53108647.70	3.00	54701907.13	
	Description:- MS Items Provision of Cover Shed for 21 Wagons (315 x 14= 4410 sqm) of CPWD DSR 2021-Ver-2 Items.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-B -MS Items Provision of Drainage facilities of CPWD DSR 2021-Ver-2 Items for the work of MS Items Upgradation/modernisation of infrastructures od STR station on PA-Miraj section under ADEN/STR.							10934929.18	Above/ Below/Par
2	Please see Item Breakup for details.				10616436.10	3.00	10934929.18	
	Description:- Part-B -MS Items Provision of Drainage facilities of CPWD DSR 2021-Ver-2 Items.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-C -MS Items Rest Room for Hamal with area 300 sqm additional area for toilet & bathroom facilities (Toilet-5, Bathroom-5, Shower-5 & Urinal-5) of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							10019708.73	Above/ Below/Par
3	Please see Item Breakup for details.				9727872.55	3.00	10019708.73	
	Description:- Part-C -MS Items Rest Room for Hamal with area 300 sqm additional area for toilet & bathroom facilities (Toilet-5, Bathroom-5, Shower-5 & Urinal-5) of CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

Schedule () A-Part-D -MS Provision of merchant room 120 sqm Items CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							4277402.03	Above/ Below/Par
4	Please see Item Breakup for details.			4152817.50	3.00		4277402.03	
	Description:- Part-D -MS Provision of merchant room 120 sqm Items CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-E-MS Provision of New CGS office 60 sqm of CPWD DSR 2021-Ver-2 for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							2432051.66	Above/ Below/Par
5	Please see Item Breakup for details.			2361215.20	3.00		2432051.66	
	Description:- Part-E-MS Provision of New CGS office 60 sqm of CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-F MS Provision of store room of size 70 sqm items of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							2661069.27	Above/ Below/Par
6	Please see Item Breakup for details.			2583562.40	3.00		2661069.27	
	Description:- Part-F MS Provision of store room of size 70 sqm items of CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-G-MS Provision of CCI of size 30 sqm with toilet facilities Items of CPWD DSR 2021 Ver-2 for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							1950228.37	Above/ Below/Par
7	Please see Item Breakup for details.			1893425.60	3.00		1950228.37	
	Description:- Part-G-MS Provision of CCI of size 30 sqm with toilet facilities Items of CPWD DSR 2021 Ver-2 items.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-H MS Provision of Drinking water facilities items of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							3617943.44	Above/ Below/Par
8	Please see Item Breakup for details.			3512566.45	3.00		3617943.44	
	Description:- Part-H MS Provision of Drinking water facilities items of CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-I MS Repairs to approach road with RCC concrete items of CPWD DSR 2021 Ver 2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							3001207.82	Above/ Below/Par
9	Please see Item Breakup for details.			2913794.00	3.00		3001207.82	
	Description:- Part-I MS Repairs to approach road with RCC concrete items of CPWD DSR 2021 Ver 2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Part-J MS Items Development of approach road with RCC concrete of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.							806367.84	Above/ Below/Par
10	Please see Item Breakup for details.			782881.40	3.00		806367.84	
	Description:- Part-J MS Items Development of approach road with RCC concrete of CPWD DSR 2021-Ver-2 Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

Schedule () A-Part-K MS Items DProvision of toilet for hammal in middle of circulating area (04 toilet & 04 urinal of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.				1741935.28	Above/ Below/Par
11	Please see Item Breakup for details.	1691199.30	3.00	1741935.28	
Description:- Part-K MS Items Provision of toilet for hammal in middle of circulating area (04 toilet & 04 urinal of CPWD DSR 2021-Ver-2 Items					

3. ITEM BREAKUP

Schedule	Schedule A-Part-A -MS Items Provision of Cover Shed for 21 Wagons (315 x 14= 4410 sqm) of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 1	MS Items Provision of Cover Shed for 21 Wagons (315 x 14= 4410 sqm) of CPWD DSR 2021-Ver-2 Items.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
1	2.6.1	All kinds of soil	cum	1100	205.45	225995
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.7.1	Ordinary rock	cum	200	412.95	82590
3	2.7.3	Hard rock (blasting prohibited)	cum	150	1184.3	177645
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	110	7365.15	810166.5
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
5	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	1500	307.95	461925
	5.22S	STEEL REINFORCEMENT				
	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
6	5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	19200	89.65	1721280
	5.33S	DESIGN MIX CONCRETE				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
7	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	442	8683.8	3838239.6
	10.0	STEEL WORK				
8	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	118950	93.05	11068297.5
9	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	209557	111.95	23459906.15
10	10.19	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	Kg	26280	88.5	2325780
	12.0	ROOFING				
	12.15	SHEET ROOFING				
	12.1	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
11	12.1.3	0.63 mm thick with zinc coating not less than 275 gm/ sqm	Sqm	8673	978	8482194
	12.4	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete.				
12	12.4.2	0.63 mm thick with zinc coating not less than 275 gm/sqm	Metre	315	750.85	236517.75

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

13	12.8	Providing reinforced by organic fibres and/or inorganic synthetic fibres cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	Sqm	472	462.1	218111.2
					Total	53108647.70
Schedule	Schedule A-Part-B -MS Items Provision of Drainage facilities of CPWD DSR 2021-Ver-2 Items for the work of MS Items Upgradation/modernisation of infrastructures od STR station on PA-Miraj section under ADEN/STR.					
Item- 2	Part-B -MS Items Provision of Drainage facilities of CPWD DSR 2021-Ver-2 Items.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	1.0	CARRIAGE OF MATERIALS				
	1.1	By Mechanical Transport including loading,unloading and stacking				
	1.1.2	Earth				
1	1.1.2.2	2km	cum	6615	203.98	1349327.7
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.6.1	All kinds of soil	cum	3000	205.45	616350
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3	2.7.1	Ordinary rock	cum	3000	412.95	1238850
4	2.7.3	Hard rock (blasting prohibited)	cum	615	1184.3	728344.5
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	147	7365.15	1082677.05
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
6	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	2800	307.95	862260
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
7	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	21000	89.65	1882650
	5.33S	DESIGN MIX CONCRETE				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
8	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	322	8683.8	2796183.6
	12.0	ROOFING				
	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
9	12.41.2	110 mm diameter	Metre	187	319.75	59793.25
					Total	10616436.10
Schedule	Schedule A-Part-C -MS Items Rest Room for Hamal with area 300 sqm additional area for toilet & bathroom facilities (Toilet-5, Bathroom-5, Shower-5 & Urinal-5) of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 3	Part-C -MS Items Rest Room for Hamal with area 300 sqm additional area for toilet & bathroom facilities (Toilet-5, Bathroom-5, Shower-5 & Urinal-5) of CPWD DSR 2021-Ver-2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	1.0	CARRIAGE OF MATERIALS				
	1.1	By Mechanical Transport including loading,unloading and stacking				
	1.1.2	Earth				
1	1.1.2.2	2km	cum	2000	203.98	407960
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.6.1	All kinds of soil	cum	150	205.45	30817.5

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3	2.7.1	Ordinary rock	cum	50	412.95	20647.5
4	2.7.3	Hard rock (blasting prohibited)	cum	50	1184.3	59215
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	15	7365.15	110477.25
	4.5S	CEMENT CONCRETE PRECAST				
	4.5	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), cost of required Centering complete.				
6	4.5.1	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20mm nominal size derived from natural sources)	cum	10	9277.75	92777.5
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
7	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	2000	307.95	615900
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
8	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	13000	89.65	1165450
	5.33S	DESIGN MIX CONCRETE				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	55	8683.8	477609
	5.33A	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources and using recycled concrete aggregate (RCA) as coarse aggregate and fine aggregate within permissible utilization of 20% e a c h , Portland Pozzolana /Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33A.2	All works above plinth level up to floor V level				
10	5.33A.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	56	10122.85	566879.6
11	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	1200	688.45	826140
	6.0	MASONRY WORK				
	6.26S	EXPOSED BRICK WALL				
	6.26	Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)				
12	6.26.2	Above plinth level upto floor V level	cum	200	8565.95	1713190
	8.0	CLADDING WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
13	8.3.2	Granite work	Metre	140	418.85	58639
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				
	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
14	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	48	1881.95	90333.6
	10.0	STEEL WORK				
15	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	698	111.95	78141.1
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	350	1225.1	428785
	11.41S	VITRIFIED FLOOR TILES				
	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
17	11.56.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm	120	3908.8	469056
	12.0	ROOFING				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
18	12.41.2	110 mm diameter	Metre	100	319.75	31975
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
19	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	100	294.85	29485
	13.44S	EXTERIOR FINISHING				
	13.44	Finishing walls with water proofing cement paint of required shade :				
20	13.44.1	New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	2500	97.6	244000
	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
21	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	Sqm	3000	158.95	476850
22	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	Sqm	300	140.05	42015
	15.0	DISMANTLING AND DEMOLISHING				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	25	2007.1	50177.5
24	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	30	2928.1	87843
	15.17	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:				
25	15.17.2	Channels, angles, tees and flats	Kg	20	1.9	38
	16.0	ROAD WORK				
	16.1S	ROADS				
	16.3	Supplying and stacking at site.				
26	16.3.1	90 mm to 45 mm size stone aggregate	cum	25	1937.6	48440
27	16.3.10	Moorum	cum	300	888.3	266490
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

28	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	2	5781.35	11562.7
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
29	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid	Each	2	5426.8	10853.6
	17.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
30	17.4.2	Range of two urinal basins with 5 litre white P.V.C. automatic flushing cistern	Each	4	8115.55	32462.2
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
31	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	4	2275	9100
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.-External work				
32	18.9.1	15 mm nominal dia Pipes	Metre	250	221.35	55337.5
33	18.9.3	25 mm nominal dia Pipes	Metre	500	370.65	185325
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
34	19.6.4	300 mm dia. R.C.C. pipe	Metre	500	902.05	451025
	21.0	ALUMINIUM WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
35	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	500	433.95	216975
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
36	21.1.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	500	531.8	265900
					Total	9727872.55
Schedule	Schedule A-Part-D -MS Provision of merchant room 120 sqm Items CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 4	Part-D -MS Provision of merchant room 120 sqm Items CPWD DSR 2021-Ver-2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	1.0	CARRIAGE OF MATERIALS				
	1.1	By Mechanical Transport including loading,unloading and stacking				
	1.1.2	Earth				
1	1.1.2.2	2km	cum	400	203.98	81592
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.6.1	All kinds of soil	cum	100	205.45	20545
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3	2.7.1	Ordinary rock	cum	20	412.95	8259
4	2.7.3	Hard rock (blasting prohibited)	cum	20	1184.3	23686
	4.0	CONCRETE WORK				
	4.15	CEMENT CONCRETE (CAST IN SITU)				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	20	7365.15	147303
	4.5S	CEMENT CONCRETE PRECAST				
	4.5	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), cost of required Centering complete.				
6	4.5.1	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20mm nominal size derived from natural sources)	cum	4	9277.75	37111
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
7	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	800	307.95	246360
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
8	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	8000	89.65	717200
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	27	8683.8	234462.6

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33A	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources and using recycled concrete aggregate (RCA) as coarse aggregate and fine aggregate within permissible utilization of 20% e a c h , Portland Pozzolana /Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33A.2	All works above plinth level up to floor V level				
10	5.33A.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	27	10122.85	273316.95
11	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	250	688.45	172112.5
	6.0	MASONRY WORK				
	6.26S	EXPOSED BRICK WALL				
	6.26	Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)				
12	6.26.2	Above plinth level upto floor V level	cum	80	8565.95	685276
	8.0	CLADDING WORK				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
13	8.3.2	Granite work	Metre	60	418.85	25131
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
14	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	20	1881.95	37639
	10.0	STEEL WORK				
15	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	209	111.95	23397.55
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	150	1225.1	183765
	11.41S	VITRIFIED FLOOR TILES				
	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
17	11.56.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm	60	3908.8	234528
	12.0	ROOFING				
	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
18	12.41.2	110 mm diameter	Metre	40	319.75	12790
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
19	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	80	294.85	23588
	13.44S	EXTERIOR FINISHING				
	13.44	Finishing walls with water proofing cement paint of required shade :				
20	13.44.1	New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	1000	97.6	97600

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
21	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	Sqm	1200	158.95	190740
22	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	Sqm	120	140.05	16806
	15.0	DISMANTLING AND DEMOLISHING				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	10	2007.1	20071
24	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	10	2928.1	29281
	15.17	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:				
25	15.17.2	Channels, angles, tees and flats	Kg	10	1.9	19
	16.0	ROAD WORK				
	16.15	ROADS				
	16.3	Supplying and stacking at site.				
26	16.3.1	90 mm to 45 mm size stone aggregate	cum	20	1937.6	38752
27	16.3.10	Moorum	cum	120	888.3	106596
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
28	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	2	5781.35	11562.7
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
29	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid	Each	2	5426.8	10853.6
	17.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

30	17.4.2	Range of two urinal basins with 5 litre white P.V.C. automatic flushing cistern	Each	2	8115.55	16231.1
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
31	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	2	2275	4550
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.-External work				
32	18.9.1	15 mm nominal dia Pipes	Metre	50	221.35	11067.5
33	18.9.3	25 mm nominal dia Pipes	Metre	100	370.65	37065
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
34	19.6.4	300 mm dia. R.C.C. pipe	Metre	200	902.05	180410
	21.0	ALUMINIUM WORK				
	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
35	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	200	433.95	86790
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
36	21.1.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	200	531.8	106360

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

						Total	4152817.50
Schedule	Schedule A-Part-E-MS Provision of New CGS office 60 sqm of CPWD DSR 2021-Ver-2 for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.						
Item- 5	Part-E-MS Provision of New CGS office 60 sqm of CPWD DSR 2021-Ver-2 Items						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
	1.0	CARRIAGE OF MATERIALS					
	1.1	By Mechanical Transport including loading,unloading and stacking					
	1.1.2	Earth					
1	1.1.2.2	2km	cum	400	203.98		81592
	2.0	EARTH WORK					
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.					
2	2.6.1	All kinds of soil	cum	50	205.45		10272.5
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.					
3	2.7.1	Ordinary rock	cum	10	412.95		4129.5
4	2.7.3	Hard rock (blasting prohibited)	cum	10	1184.3		11843
	4.0	CONCRETE WORK					
	4.1S	CEMENT CONCRETE (CAST IN SITU)					
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	10	7365.15		73651.5
	4.5S	CEMENT CONCRETE PRECAST					
	4.5	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), cost of required Centering complete.					
6	4.5.1	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20mm nominal size derived from natural sources)	cum	2	9277.75		18555.5
	5.0	REINFORCED CEMENT CONCRETE					
	5.9S	FORM WORK					
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for					
7	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	400	307.95		123180
	5.22S	STEEL REINFORCEMENT					
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
8	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	4000	89.65		358600

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	13	8683.8	112889.4
	5.33A	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources and using recycled concrete aggregate (RCA) as coarse aggregate and fine aggregate within permissible utilization of 20% e a c h , Portland Pozzolana /Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33A.2	All works above plinth level up to floor V level				
10	5.33A.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	13	10122.85	131597.05
11	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	250	688.45	172112.5
	6.0	MASONRY WORK				
	6.26S	EXPOSED BRICK WALL				
	6.26	Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)				
12	6.26.2	Above plinth level upto floor V level	cum	40	8565.95	342638
	8.0	CLADDING WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
13	8.3.2	Granite work	Metre	30	418.85	12565.5
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				
	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
14	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	10	1881.95	18819.5
	10.0	STEEL WORK				
15	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	104	111.95	11642.8
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	75	1225.1	91882.5
	11.41S	VITRIFIED FLOOR TILES				
	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
17	11.56.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm	30	3908.8	117264
	12.0	ROOFING				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
18	12.41.2	110 mm diameter	Metre	20	319.75	6395
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
19	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	400	294.85	117940
	13.44S	EXTERIOR FINISHING				
	13.44	Finishing walls with water proofing cement paint of required shade :				
20	13.44.1	New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	500	97.6	48800
	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
21	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	Sqm	600	158.95	95370
22	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	Sqm	60	140.05	8403
	15.0	DISMANTLING AND DEMOLISHING				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	5	2007.1	10035.5
24	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	10	2928.1	29281
	15.17	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:				
25	15.17.2	Channels, angles, tees and flats	Kg	10	1.9	19
	16.0	ROAD WORK				
	16.1S	ROADS				
	16.3	Supplying and stacking at site.				
26	16.3.1	90 mm to 45 mm size stone aggregate	cum	10	1937.6	19376
27	16.3.10	Moorum	cum	60	888.3	53298
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

28	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	1	5781.35	5781.35
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
29	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid	Each	1	5426.8	5426.8
	17.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
30	17.4.2	Range of two urinal basins with 5 litre white P.V.C. automatic flushing cistern	Each	1	8115.55	8115.55
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
31	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	1	2275	2275
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.-External work				
32	18.9.1	15 mm nominal dia Pipes	Metre	50	221.35	11067.5
33	18.9.3	25 mm nominal dia Pipes	Metre	100	370.65	37065
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
34	19.6.4	300 mm dia. R.C.C. pipe	Metre	125	902.05	112756.25
	21.0	ALUMINIUM WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
35	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	100	433.95	43395
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
36	21.1.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	100	531.8	53180
					Total	2361215.20
Schedule	Schedule A-Part-K MS Items DProvision of toilet for hammal in middle of circulating area (04 toilet & 04 urinal of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 11	Part-K MS Items Provision of toilet for hammal in middle of circulating area (04 toilet & 04 urinal of CPWD DSR 2021-Ver-2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
1	2.6.1	All kinds of soil	cum	30	205.45	6163.5
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.7.1	Ordinary rock	cum	15	412.95	6194.25
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
3	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	6	7365.15	44190.9
	5.0	REINFORCED CEMENT CONCRETE				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
4	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	520	307.95	160134
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
5	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	2400	89.65	215160
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
6	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	27	8683.8	234462.6
	6.0	MASONRY WORK				
	6.2	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:				
7	6.2.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	35	5746.8	201138
	7.0	STONE WORK				
	7.6S	COURSED RUBBLE MASONRY				
	7.7	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :				
8	7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	17	7380.35	125465.95
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				
	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
9	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	10	1881.95	18819.5
	10.0	STEEL WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

10	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	1500	93.05	139575
11	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	698	111.95	78141.1
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
12	11.37A	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	70	938.5	65695
	12.0	ROOFING				
	12.1S	SHEET ROOFING				
	12.1	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
13	12.1.1	1.00 mm thick with zinc coating not less than 275 gm/sqm	Sqm	75	1320.35	99026.25
	12.4	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete.				
14	12.4.1	0.80 mm thick with zinc coating not less than 275 gm/sqm	Metre	7	822.15	5755.05
	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
15	12.41.2	110 mm diameter	Metre	30	319.75	9592.5
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
16	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	20	294.85	5897
	16.0	ROAD WORK				
	16.1S	ROADS				
	16.3	Supplying and stacking at site.				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

17	16.3.10	Moorum	cum	80	888.3	71064
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
18	17.1.2	Stainless Steel AISI-304(18/8) Orissa pattern W.C. pan of size 585x480 mm with flush pipe and integrated type foot rests	Each	4	10076.15	40304.6
	17.5	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required :				
19	17.5.1	Single half stall urinal with 5 litre P.V.C. automatic flushing cistern	Each	4	10128.3	40513.2
	17.10	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				
	17.10.2	Kitchen sink without drain board				
20	17.10.2.1	610x510 mm bowl depth 200 mm	Each	4	4274.4	17097.6
	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	17.28.1	Semi rigid pipe				
21	17.28.1.2	40 mm dia	Each	4	101.65	406.6
	17.69	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour.				
22	17.69.1	Waste coupling 31 mm dia of 79 mm length and 62mm breadth weighing not less than 45 gms	Each	4	103	412
	17.70	Providing and fixing PTMT Bottle Trap for Wash basin and sink.				
23	17.70.1	Bottle trap 31mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 260 gms	Each	4	325.1	1300.4
	18.0	WATER SUPPLY				
	18.75	C.P.V.C. PIPES				
	18.12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.-External work				
24	18.12.1	15 mm dia nominal bore	Metre	50	267.5	13375
25	18.12.3	25 mm dia nominal bore	Metre	100	417.95	41795
	18.31S	C.I. SLUICE VALVES/ FIRE HYDRANTS & FIXTURES				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

26	18.48A	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to IS : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately.	Litre	5000	9.7	48500
	18.54S	PTMT FITTINGS				
	18.54	Providing and fixing PTMT bib cock of approved quality and colour.				
27	18.54.4	15 mm nominal bore, 90 mm long, weighing not less than 93 gms	Each	6	170.05	1020.3
					Total	1691199.30
Schedule	Schedule A-Part-H MS Provision of Drinking water facilities items of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 8	Part-H MS Provision of Drinking water facilities items of CPWD DSR 2021-Ver-2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
1	2.6.1	All kinds of soil	cum	200	205.45	41090
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.7.1	Ordinary rock	cum	200	412.95	82590
3	2.7.3	Hard rock (blasting prohibited)	cum	240	1184.3	284232
	5.0	REINFORCED CEMENT CONCRETE				
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
4	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	9	8683.8	78154.2
	10.0	STEEL WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

5	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	2000	93.05	186100
6	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	698	111.95	78141.1
	12.0	ROOFING				
	12.1S	SHEET ROOFING				
	12.1	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
7	12.1.1	1.00 mm thick with zinc coating not less than 275 gm/sqm	Sqm	30	1320.35	39610.5
	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
8	12.41.2	110 mm diameter	Metre	300	319.75	95925
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
9	13.1.2	1:6 (1 cement: 6 fine sand)	Sqm	1	282	282
	17.0	SANITARY INSTALLATIONS				
	17.10	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				
	17.10.2	Kitchen sink without drain board				
10	17.10.2.1	610x510 mm bowl depth 200 mm	Each	10	4274.4	42744
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.-External work				
11	18.12.1	15 mm dia nominal bore	Metre	200	267.5	53500
12	18.12.2	20 mm dia nominal bore	Metre	300	315.35	94605
13	18.12.3	25 mm dia nominal bore	Metre	500	417.95	208975
14	18.12.6	50 mm dia nominal bore	Metre	1000	654.2	654200
15	18.12.8	80 mm dia nominal bore	Metre	1500	919.1	1378650

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
16	18.13.1	25 to 40 mm nominal bore	Each	6	757.1	4542.6
17	18.13.2	50 to 80 mm nominal bore	Each	4	1513.7	6054.8
	18.54S	PTMT FITTINGS				
	18.54	Providing and fixing PTMT bib cock of approved quality and colour.				
18	18.54.4	15 mm nominal bore, 90 mm long, weighing not less than 93 gms	Each	25	170.05	4251.25
	18.55	Providing and fixing PTMT stop cock of approved quality and colour.				
19	18.55.1	15 mm nominal bore, 86 mm long, weighing not less than 88 gms	Each	10	103.15	1031.5
	18.59S	AIR VALVE & WATER METER (BULK TYPE)				
	18.60	Providing and fixing enclosed type water meter (bulk type) conforming to IS : 2373 and tested by Municipal Board complete with bolts, nuts, rubber insertions etc. (The tail pieces if required will be paid separately) :				
20	18.60.1	80 mm dia nominal bore	Each	2	3266.1	6532.2
	18.61	Providing and fixing C.I. dirt box strainer for bulk type water meter with nuts, bolts, rubber insertions etc. complete conforming to IS : 2373 :				
21	18.61.4	200 mm dia	Each	2	11712.65	23425.3
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
22	19.6.2	150 mm dia. R.C.C. pipe	Metre	300	493.1	147930
					Total	3512566.45
Schedule	Schedule A-Part-I MS Repairs to approach road with RCC concrete items of CPWD DSR 2021 Ver 2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 9	Part-I MS Repairs to approach road with RCC concrete items of CPWD DSR 2021 Ver 2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
1	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	400	307.95	123180
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
2	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	2760	89.65	247434
	5.33S	DESIGN MIX CONCRETE				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
3	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	42	8683.8	364719.6
	7.0	STONE WORK				
	7.6S	COURSED RUBBLE MASONRY				
	7.7	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :				
4	7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	240	7380.35	1771284
	10.0	STEEL WORK				
5	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	3492	111.95	390929.4
	13.0	FINISHING				
	13.33S	POINTING ON STONE WORK				
	13.33	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) :				
6	13.33.2	Raised and cut pointing	Sqm	28	580.25	16247
					Total	2913794.00
Schedule	Schedule A-Part-J MS Items Development of approach road with RCC concrete of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 10	Part-J MS Items Development of approach road with RCC concrete of CPWD DSR 2021-Ver-2 Items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	16.0	ROAD WORK				
	16.1S	ROADS				
1	16.1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	Sqm	150	180.5	27075
	16.3	Supplying and stacking at site.				
2	16.3.1	90 mm to 45 mm size stone aggregate	cum	35	1937.6	67816
3	16.3.2	63 mm to 45 mm size stone aggregate	cum	15	1624.5	24367.5
4	16.3.3	53 mm to 22.4 mm size stone aggregate	cum	12	1837.25	22047
5	16.3.8	Red bajri	cum	10	1557.25	15572.5

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

6	16.4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .	cum	62	865.8	53679.6
	16.42S	CONCRETE PAVEMENTS				
7	16.42	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	cum	23	7399.2	170181.6
	16.43	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately).				
8	16.43.2	Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	cum	38	10006.65	380252.7
9	16.44	Extra for providing and mixing hardening compound of approved quality as per manufacturer's specification in cement concrete.	Litre	10	48.15	481.5
	16.46	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge.				
10	16.46.1	Using grade 'A' sealing compound conforming to IS: 1834.	per cm depth per cm width per metre length	450	7.5	3375
	16.49S	MISCELLANEOUS				
	16.70	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge.				
11	16.70.2	Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade	Sqm	20	901.65	18033

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

						Total	782881.40
Schedule	Schedule A-Part-F MS Provision of store room of size 70 sqm items of CPWD DSR 2021-Ver-2 Items for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.						
Item- 6	Part-F MS Provision of store room of size 70 sqm items of CPWD DSR 2021-Ver-2 Items						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount	
	1.0	CARRIAGE OF MATERIALS					
	1.1	By Mechanical Transport including loading,unloading and stacking					
	1.1.2	Earth					
1	1.1.2.2	2km	cum	400	203.98		81592
	2.0	EARTH WORK					
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.					
2	2.6.1	All kinds of soil	cum	80	205.45		16436
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.					
3	2.7.1	Ordinary rock	cum	20	412.95		8259
4	2.7.3	Hard rock (blasting prohibited)	cum	10	1184.3		11843
	4.0	CONCRETE WORK					
	4.1S	CEMENT CONCRETE (CAST IN SITU)					
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	15	7365.15		110477.25
	4.5S	CEMENT CONCRETE PRECAST					
	4.5	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), cost of required Centering complete.					
6	4.5.1	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20mm nominal size derived from natural sources)	cum	2	9277.75		18555.5
	5.0	REINFORCED CEMENT CONCRETE					
	5.9S	FORM WORK					
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for					
7	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	400	307.95		123180
	5.22S	STEEL REINFORCEMENT					
	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.					

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

8	5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	4000	89.65	358600
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	18	8683.8	156308.4
	5.33A	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources and using recycled concrete aggregate (RCA) as coarse aggregate and fine aggregate within permissible utilization of 20% e a c h , Portland Pozzolana /Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33A.2	All works above plinth level up to floor V level				
10	5.33A.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	18	10122.85	182211.3
11	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	250	688.45	172112.5
	6.0	MASONRY WORK				
	6.26S	EXPOSED BRICK WALL				
	6.26	Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

12	6.26.2	Above plinth level upto floor V level	cum	50	8565.95	428297.5
	8.0	CLADDING WORK				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
13	8.3.2	Granite work	Metre	40	418.85	16754
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				
	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
14	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	10	1881.95	18819.5
	10.0	STEEL WORK				
15	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	110	111.95	12314.5
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	80	1225.1	98008
	11.41S	VITRIFIED FLOOR TILES				
	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
17	11.56.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm	40	3908.8	156352
	12.0	ROOFING				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
18	12.41.2	110 mm diameter	Metre	30	319.75	9592.5
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
19	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	45	294.85	13268.25
	13.44S	EXTERIOR FINISHING				
	13.44	Finishing walls with water proofing cement paint of required shade :				
20	13.44.1	New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	550	97.6	53680
	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
21	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	Sqm	650	158.95	103317.5
22	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	Sqm	70	140.05	9803.5
	15.0	DISMANTLING AND DEMOLISHING				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	5	2007.1	10035.5
24	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	10	2928.1	29281
	15.17	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:				
25	15.17.2	Channels, angles, tees and flats	Kg	10	1.9	19
	16.0	ROAD WORK				
	16.1S	ROADS				
	16.3	Supplying and stacking at site.				
26	16.3.1	90 mm to 45 mm size stone aggregate	cum	10	1937.6	19376
27	16.3.10	Moorum	cum	70	888.3	62181
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

28	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	1	5781.35	5781.35
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
29	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid	Each	1	5426.8	5426.8
	17.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
30	17.4.2	Range of two urinal basins with 5 litre white P.V.C. automatic flushing cistern	Each	1	8115.55	8115.55
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
31	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	1	2275	2275
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.-External work				
32	18.9.1	15 mm nominal dia Pipes	Metre	50	221.35	11067.5
33	18.9.3	25 mm nominal dia Pipes	Metre	100	370.65	37065
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
34	19.6.4	300 mm dia. R.C.C. pipe	Metre	130	902.05	117266.5
	21.0	ALUMINIUM WORK				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
35	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	120	433.95	52074
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
36	21.1.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	120	531.8	63816
					Total	2583562.40
Schedule	Schedule A-Part-G-MS Provision of CCI of size 30 sqm with toilet facilities Items of CPWD DSR 2021 Ver-2 for the work of Upgradation/modernisation of infrastructures of STR station on PA-Miraj section under ADEN/STR.					
Item- 7	Part-G-MS Provision of CCI of size 30 sqm with toilet facilities Items of CPWD DSR 2021 Ver-2 items.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	1.0	CARRIAGE OF MATERIALS				
	1.1	By Mechanical Transport including loading,unloading and stacking				
	1.1.2	Earth				
1	1.1.2.2	2km	cum	300	203.98	61194
	2.0	EARTH WORK				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
2	2.6.1	All kinds of soil	cum	80	205.45	16436
	2.7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3	2.7.1	Ordinary rock	cum	20	412.95	8259
4	2.7.3	Hard rock (blasting prohibited)	cum	10	1184.3	11843
	4.0	CONCRETE WORK				
	4.15	CEMENT CONCRETE (CAST IN SITU)				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	10	7365.15	73651.5
	4.5S	CEMENT CONCRETE PRECAST				
	4.5	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), cost of required Centering complete.				
6	4.5.1	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20mm nominal size derived from natural sources)	cum	10	9277.75	92777.5
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
7	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	300	307.95	92385
	5.22S	STEEL REINFORCEMENT				
	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
8	5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	3000	89.65	268950
	5.33S	DESIGN MIX CONCRETE				
	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	18	8683.8	156308.4

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	5.33A	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources and using recycled concrete aggregate (RCA) as coarse aggregate and fine aggregate within permissible utilization of 20% e a c h , Portland Pozzolana /Ordinary Portland/Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33A.2	All works above plinth level up to floor V level				
10	5.33A.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	18	10122.85	182211.3
11	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	160	688.45	110152
	6.0	MASONRY WORK				
	6.26S	EXPOSED BRICK WALL				
	6.26	Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)				
12	6.26.2	Above plinth level upto floor V level	cum	20	8565.95	171319
	8.0	CLADDING WORK				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
13	8.3.2	Granite work	Metre	20	418.85	8377
	9.0	WOOD AND P.V.C. WORK				
	9.16	Providing and fixing 25 mm thick shutters for cup board etc. :				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
14	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	4	1881.95	7527.8
	10.0	STEEL WORK				
15	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	83	111.95	9291.85
	11.0	FLOORING				
	11.37S	CERAMIC GLAZED TILES				
16	11.40	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	80	1225.1	98008
	11.41S	VITRIFIED FLOOR TILES				
	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
17	11.56.1	Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm	20	3908.8	78176
	12.0	ROOFING				
	12.40	Providing, fixing and embedding sand cast iron accessories for rain water pipes in the masonry surrounded with 12 mm thick cement mortar of the same mix, as that of masonry (lead caulking will be paid for separately):				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
18	12.41.2	110 mm diameter	Metre	20	319.75	6395
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.1	12 mm cement plaster of mix :				
19	13.1.1	1:4 (1 cement: 4 fine sand)	Sqm	20	294.85	5897
	13.44S	EXTERIOR FINISHING				
	13.44	Finishing walls with water proofing cement paint of required shade :				
20	13.44.1	New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm	400	97.6	39040

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	13.48	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :				
21	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	Sqm	400	158.95	63580
22	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	Sqm	40	140.05	5602
	15.0	DISMANTLING AND DEMOLISHING				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	10	2007.1	20071
24	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	20	2928.1	58562
	15.17	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in:				
25	15.17.2	Channels, angles, tees and flats	Kg	20	1.9	38
	16.0	ROAD WORK				
	16.15	ROADS				
	16.3	Supplying and stacking at site.				
26	16.3.1	90 mm to 45 mm size stone aggregate	cum	10	1937.6	19376
27	16.3.10	Moorum	cum	20	888.3	17766
	17.0	SANITARY INSTALLATIONS				
	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
28	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	1	5781.35	5781.35
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
29	17.2.2	W.C. pan with ISI marked black solid plastic seat and lid	Each	1	5426.8	5426.8
	17.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

30	17.4.2	Range of two urinal basins with 5 litre white P.V.C. automatic flushing cistern	Each	2	8115.55	16231.1
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
31	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	1	2275	2275
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.-External work				
32	18.9.1	15 mm nominal dia Pipes	Metre	40	221.35	8854
33	18.9.3	25 mm nominal dia Pipes	Metre	60	370.65	22239
	19.0	DRAINAGE				
	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:				
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
34	19.6.4	300 mm dia. R.C.C. pipe	Metre	80	902.05	72164
	21.0	ALUMINIUM WORK				
	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
35	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	80	433.95	34716
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
36	21.1.2.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	80	531.8	42544

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

	Total	1893425.60
--	--------------	-------------------

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover.	No	No	Allowed (Mandatory)
1.1	The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Not Allowed
1.2	In case of newly formed partnership firm, the credentials of individual partners from previous propriety firm(s) or dissolved previous partnership firm(s) or split previous partnership firm(s), shall be considered only to the extent of their share in previous entity on the date of dissolution / split and their share in newly formed partnership firm. For example, a partner A had 30% share in previous entity and his share in present partnership firm is 20%. In the present tender under consideration, the credentials of partner A will be considered to the extent of 0.3*0.2*value of the work done in the previous entity. For this purpose, the tenderer shall submit along with his bid all the relevant documents which include copy of previous partnership deed(s), dissolution deed(s) and proof of surrender of PAN No.(s) in case of dissolution of partnership firm(s) etc.	No	No	Not Allowed
1.2.1	In case of existing partnership firm, if any one or more partners quit the partnership firm, the credentials of remaining partnership firm shall be re-worked out i.e., the quitting partner(s) shall take away his credentials to the extent of his share on the date of quitting the partnership firm(e.g. in a partnership firm of partners A, B & C having share 30%, 30% & 40% respectively and credentials of Rs 10 crore; in case partner C quits the firm, the credentials of this partnership firm shall remain as Rs 6 crore). For this purpose, the tenderer shall submit along with his bid all the relevant documents which include copy of previous partnership deed(s), dissolution deed(s) and proof of surrender of PAN No.(s) in case of dissolution of partnership firm(s) etc.	No	No	Not Allowed
1.2.2	In case of existing partnership firm if any new partner(s) joins the firm without any modification in the name and PAN/TAN no. of the firm, the credentials of partnership firm shall get enhanced to the extent of credentials of newly added partner(s) on the same principles as mentioned in item 6 above. For this purpose, the tenderer shall submit along with his bid all the relevant documents which include copy of previous partnership deeds, dissolution/splitting deeds and proof of surrender of PAN No.(s) in case of dissolution of partnership firm etc.	No	No	Not Allowed

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

1	Technical Eligibility Criteria: (a)The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i)Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii)Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii)One similar work costing not less than the amount equal to 60% of advertised value of the tender (b) (1)In case of tenders for composite works(e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i)Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii)Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii)One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b)(2)In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (3) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 of the Standard General Conditions of Contractor through subcontractor fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Engineer in writing. However, if required in tender documents by way of Special Conditions, a formal agreement duly notarised, legally enforceable in the court of law, shall be executed by the main contractor with the subcontractor for the component(s) of work proposed to be executed by the subcontractor(s), and shall be submitted along with the offer for considering subletting of that scope of work towards fulfillment of technical eligibility. Such subcontractor must fulfill technical eligibility criteria as follows: The subcontractor shall have successfully completed at least one work similar to work proposed for subcontract, costing not less than 35% value of work to be subletted, in last 5 years, ending last day of month previous to the one in which tender is invited through a works contract. Note: for subletting of work costing up to Rs 50 lakh, no previous work experience of subcontractor shall be asked for by the Railway.	No	No	Allowed (Mandatory)
1.1	Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Not Allowed
1.2	Para 1.2 & its sub para of standard financial criteria are also applicable during evaluation of technical credential of partnership firm.	No	No	Not Allowed
1.3	Defination of Similar Work :- 'Any type of civil work viz building up to G+4 and structure work, pipe line, under ground and overhead tanks, foundation treatment works in any Railway embankment /cutting, any earth work, cover over platform, bore wells, level crossing works including lifting barriers, cement concrete apron works'.	No	No	Not Allowed

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

1	Tenderers will examine the various provisions of The Central Goods and Services Tax Act,2017(CGST)/ Integrated Goods and Services Tax Act, 2017 (IGST)/ Union Territory Goods and Services Tax Act, 2017(UTGST)/ respective state's State Goods and Services Tax Act (SGST) also, as notified by Central/State Govt.& as amended from time to time and applicable taxes before bidding. Tenderers will ensure that full benefit of Input Tax Credit (ITC) likely to be availed by them is duly considered while quoting rates. The successful tenderer who is liable to be registered under CGST/IGST/UTGST/SGST Act shall submit GSTIN along with other details required under CGST/IGST/UTGST/SGST Act to railway immediately after the award of contract, without which no payment shall be released to the Contractor. The Contractor shall be responsible for deposition of applicable GST to the concerned authority. In case the successful tenderer is not liable to be registered under CGST/IGST/UTGST/ SGST Act, the railway shall deduct the applicable GST from his/their bills under reverse charge mechanism (RCM) and deposit the same to the concerned authority. Contractor shall be liable to pay/refund the amount collected as GST to the Indian Railways along with interest and penalties, if any imposed by the authorities, in case GST input tax credit of Indian Railways is denied/rejected by the tax authorities due to reasons mentioned below but not limited to: Wrong/incorrect invoices issued by Contractor ; No-filing of GST returns; Non-payment of GST collected from Indian Railways to the authorities; Any other non-compliance done by Contractor; Retention Money: Any payment liable to be paid by Indian Railways to contractor against the goods or services or both supplied by such contractor to Indian Railways shall be kept on hold in case supplier makes any non-compliance of any of the GST law provisions including non-reporting of invoices in GST returns. Such payment shall be released after proper verification of records and availability of ITC to Indian Railways as per provisions of GST Law. General Indemnity: Contractor hereby agrees to indemnify and hold harmless the Indian Railways from and against any and all losses, including loss on account of Input Tax Credit and all losses incurred by the Indian Railways relating to or arising out of or in connection with any actual or threatened claim, legal action, proceedings, prosecution or inquiry by or against the Indian Railways arising out, directly or indirectly, of failure by the contractor to comply with the provisions of GST and related laws, or based upon or arising from any failure by the Contractor {After award of LOA it should be indemnify otherwise action may be taken by competent authority and will be binding upon contractor}.(ACS-6 dtd 21.12.2023	No	No	Allowed (Mandatory)
---	---	----	----	------------------------

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

2	The Bid Security shall be deposited either in cash through e-payment gateway or submitted as Bank Guarantee bond from a scheduled commercial bank of India or as mentioned in tender documents. The Bank Guarantee bond shall be as per Annexure-VIA and shall be valid for a period of 90days beyond the bid validity period. In case, submission of Bid Security in the form of Bank Guarantee, following shall be ensured: (i).A scanned copy of the Bank Guarantee shall be uploaded on e-Procurement Portal (IREPS) while applying to the tender. (ii).The original Bank Guarantee should be delivered to Chief Office Superintendent Rate before closing date for submission of bids i.e., excluding the last date of submission of bids. (ACS-5 dtd 20.10.02023). (iii)Non submission of scanned copy of Bank Guarantee with the bid on tendering portal (IREPS) and/or non submission of original Bank Guarantee within the specified period shall lead to summary rejection of bid. (iv)The Tender Security shall remain valid for a period of 90 days beyond the validity period for the Tender. (v) The details of the BG, physically submitted should match with the details available in the scanned copy and the data entered during bid submission time, failing which the bid will be rejected (vi).The Bank Guarantee shall be placed in an envelope, which shall be sealed. The envelope shall clearly bear the identification "Bid for the ***** Project" and shall clearly indicate the name and address of the Bidder. In addition, the Bid Due Date should be indicated on the right hand top corner of the envelope. (vii)The envelope shall be addressed to the officer and address as mentioned in the tender document. (viii).If the envelope is not sealed and marked as instructed above, the Railway assumes no responsibility for the misplacement or premature opening of the contents of the Bid submitted and consequent losses, if any, suffered by the Bidder.	No	No	Allowed (Mandatory)
3	Tenderers should show discount in the rate schedule only, instead of anywhere else in the offer. Discounts not shown at designated place will be summarily ignored for assigning inter-se ranking of offers. Conditional discount will not be considered for adjudging the inter-se position i.e. rate quoted without any conditions attached (viz. Discount/ Rebates having linkages to quantity, rates payment etc.) will only be considered for evaluation purpose. In other words, discounted rates linked to quantities, rates, prompt payment etc. will be ignored for determining inter-se position. Railway, however reserves the right to use the discounted rate/ rates considered workable and appropriate, for counter offer to the successful tenderers	No	No	Not Allowed
4	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per the recommendations by the 47th GST Council Meeting in relation to changes in Tax rates, circulated by Railway Board vide L.No.2017/ACII/1/6/GST/Main/Vol.-III, dated 05-07-2022, the GST rates on Railway works contract has been revised from existing 12% to 18%. The clarification mentioned in the Railway Board's letter is attached in tender document. Therefore, Bidders are requested to quote their rates including 18% GST.	No	No	Not Allowed
2	Spl Eligibility Condition, Scope of Work, Special conditions attached to GCC	No	No	Not Allowed
2.1	In terms of HQ's letter No. W.187.R.GCC dated 24.05.2019, "If any contract is terminated under clause 62 of GCC on contractor's fault, then that contractor shall be temporarily debarred from participation in any tender in that division for ONE YEAR, If so decided by the Tender Accepting Authority.	No	No	Not Allowed
2.1.1	Tenderer should quote their offer with all-inclusive rates.	No	No	Not Allowed

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

2.2	In case creation of unsafe working due to infringement/entanglement of P. Way materials (Rails, Sleeper, tec.) or/and tool & plants, deployed at worksites with running trains, a penalty of Rs. 1,00,000/- (Rs. One Lakh) shall be imposed per incident. In case of repeated such incidence, contract is liable for termination as per contract conditions. (HQ's Lt. No. W.636.T.FBWP/Tender/2017 dtd. 12.10.2021).	No	No	Not Allowed
2.3	Tenderers are requested to go through the Special Conditions for Letter of Credit.	No	No	Not Allowed
2.4	Spl Eligibility Condition, Scope of Work, Special conditions attached to GCC . The tender Document of the subjected work is in conformity with Indian Railways Standard General Conditions of Contract - April 2022 with latest correction slip No 10, the perspective Tenderers are requested to go through the Tender Document before offering their offers. Applicability of Price Variation Clause (PVC) depends on fulfillment of condition of Para 46.A1 of Indian Railways Standard General Conditions of Contract April 2022-part II corrected upto ACS 10.	No	No	Not Allowed
2.5	Applicability of Price Variation Clause (PVC) depends on fulfilment of condition of Para 46.A1 of Indian Railways Standard General Conditions of Contract April 2022-part II corrected up to ACS 7.	No	No	Not Allowed
2.6	Documentary proof - Tenderer should submit scanned copy documentary proof in regard for fulfilling the Technical /financial eligibility criteria along-with their offer (for details refer attached documents). If the tenderers do not submit any proof of meeting with the eligibility criteria as laid down in the tender conditions, the offer shall be considered as incomplete and shall be summarily rejected. Documents submitted in support of eligibility criteria after opening of tender will not be considered	No	No	Not Allowed
2.7	The all documents submitted should not be corrupted, if at the time of tender opening. The document submitted are not opened being corrupted, offer shall be summarily rejected.	No	No	Not Allowed
3	Contractors' measurements are applicable to Tender value above 5 crores.	No	No	Not Allowed
4	Maintenance period for this work is 6 (Six) Months.	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / Company / Registered Society / Registered Trust / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. The tenderer(s) shall enclose the attested copies of the constitution of their concern, and copy of PAN Card along with their tender. Tender Documents in such cases are to be signed by such persons as may be legally competent to sign them on behalf of the firm, company, association, trust or society, as the case may be. Following set of documents shall be submitted by the tenderer in reference to their constitutional concern. Offers of bidder without these documents will be summarily rejected.	No	No	Allowed (Mandatory)
1.1	Company registered under Company Act:-(i) The copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company (ii)A copy of Certificate of Incorporation (iii)A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company.	No	No	Not Allowed

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

1.2	HUF:-(i)A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family (HUF) and he has the authority, power and consent given by other members to act on behalf of HUF.	No	No	Not Allowed
1.3	LLP:-(i)A copy of LLP Agreement (ii)A copy of Certificate of Incorporation (iii)A copy of Power of Attorney/Authorization issued by the LLP in favour of the individual to sign the tender on behalf of the LLP and create liability against the LLP. (iv) An undertaking by all partners of the LLP that they are not blacklisted or debarred by Railways or any other Ministry / Department of the Govt. of India from participation in tenders / contracts as on the date of submission of bids, either in their individual capacity or in any firm/LLP or JV in which they were / are partners/members. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the Standard General Conditions of Contract.	No	No	Not Allowed
1.4	Partnership Firm :-(i)A notarized copy of the Partnership Deed or a copy of the Partnership deed registered with the Registrar. (ii)A notarized or registered copy of Power of Attorney in favor of the individual to tender for the work, sign the agreement etc. and create liability against the firm. (iii) An undertaking by all partners of the partnership firm that they are not blacklisted or debarred by Railways or any other Ministry / Department of the Govt. of India from participation in tenders / contracts as on the date of submission of bids, either in their individual capacity or in any firm/LLP in which they were / are partners/members. Any Concealment / wrong information in regard to above shall make the bid ineligible or the contract shall be determined under Clause 62 of the Standard General Conditions of Contract.	No	No	Not Allowed
1.5	Registered society: (i)A copy of Certificate of Registration (ii)A copy of Memorandum of Association of Society/Trust Deed (iii)A copy of Power of Attorney in favor of the individual to sign the tender documents and create liability against the Society/Trust. (iv)A copy of Rules & Regulations of the Society.	No	No	Not Allowed
2	Dully filled Tender Form (First Sheet as per Annexure I of tender document) shall be submitted.	Yes	Yes	Allowed (Mandatory)
3	Tenderer should submit Particulars of the Tenderer such as Name of the Firm, Constitution of the firm (Proprietary/Partnership firm/ LLP/Company/HUF/Society etc.), Name of Owner, Office Address, Phone No; email address, Key Person Name & Phone No; etc. along with the bid. Further in reference to GCC para 11; they have to submit following set of documents:- (a) List of personnel, organization available on hand and proposed to be engaged for the subject work. (b) List of plant & machinery available on hand (own) and proposed to be inducted (own and hired to be given separately) for the subject work. (c) List of works completed in the last 07 (seven) years, ending last day of month previous to the one in which tender is invited, giving description of work, organization for whom executed, approximate value of contract at the time of award, date of award and date of schedule completion of work. Date of actual start, actual completion & final value of contract should also be given. (d) List of works on hand indicating description of work, contract value, and approximate value of balance work yet to be done and date of award. (e) Audited Balance Sheet duly certified by the Chartered Accountant regarding contractual payments received in the past.	Yes	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	CheckList_1.pdf	Check List
2	TD-2024-S-38.pdf	GCC scope with spl condition etc
3	AdvanceCorrectionSlipNo10ACS-10.pdf	ASC 10

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017,

**PUNE DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: DRM-W-PA-E-Tend-2024-S-38

Closing Date/Time: 15/04/2025 15:15

issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: VIKAS KUMAR

Designation : Sr.DENS